



ITB-18-03
ADDENDUM #1 *JHM*

2018 CONCRETE REHABILITATION – ADA IMPROVEMENTS PROJECT

Date: Feb 26, 2018
Bid Number: ITB-18-03
Bid Due Date: TUESDAY, MARCH 5, 2018 BY 1:00 PM OUR CLOCK

The following information is provided to all prospective bidders and is hereby made a part of the above bid documents. Bidders must acknowledge this Addendum 1 with their bid. It is a total of two pages, including the attached REVISED Bid Schedule page 18.

CLARIFICATION, ADDITIONAL INFORMATION, AND CHANGES:

1. Where do I find the info for Items 604A & 604B or any details?

Item 604A Reconstruct WR Curb Inlet (Double)

The intent of this item is to remove the sidewalk behind the inlet structure and remove the concrete curb in front of the inlet, and remove all unsound concrete. Clean all existing rebar and re-pour concrete to repair the existing curb inlet.

Item 604B Reconstruct Valley Inlet

The intent of this item is to remove damaged concrete around the existing box which is supporting the valley grate, remove all unsuitable concrete until suitable base is established. Clean all existing rebar and re-pour concrete to repair the existing valley inlet.

IMPORTANT: Please use the REVISED page 18 when submitting your bid.

Visit our City website for prebid sign in sheet, addendum, plan holders list and project updates:
www.ci.wheatridge.co.us

POINT OF CONTACT: Jennifer Nellis, Purchasing Agent, jnellis@ci.wheatridge.co.us, fax 303-234-5924, or phone 303-235-2811. Do not contact the user department, consultant, or any other staff.

ADDENDA

Bidder acknowledges receipt of the following Addenda:

BID SCHEDULE COMPANY SUBMITTING BID _____
ITB-18-03 S-PM-03-18

Bidder agrees to perform all the work described in the Contract Documents for the following unit prices or lump sums.

ITEM NO.	PAY ITEM	ESTIMATED QUANTITY	UNIT	UNIT PRICE	EXTENSION
210	Adjust Utility Box	4	EA	\$ _____	\$ _____
403A	HMA Patching CIP 4" SP-100 PG (64-22) SX	50	SY	\$ _____	\$ _____
403B	HMA Patching CIP 6" SP-100 PG (64-22) S	50	SY	\$ _____	\$ _____
412	Concrete Pavement (10")(Remove & Replace)	670	SY	\$ _____	\$ _____
604A	Reconstruct WR Curb Inlet (<i>Double</i>)	1	EA	\$ _____	\$ _____
604B	Reconstruct Valley Inlet	1	EA	\$ _____	\$ _____
608A	CDOT Curb Ramp (Type 1A) Remove & Replace	2	EA	\$ _____	\$ _____
608B	CDOT Curb Ramp (Type 1B) Remove & Replace	1	EA	\$ _____	\$ _____
608C	CDOT Curb Ramp (Type 2A) Remove & Replace	15	EA	\$ _____	\$ _____
608D	CDOT Curb Ramp (Type 2B) Remove & Replace	1	EA	\$ _____	\$ _____
608E	CDOT Curb Ramp (Type 2B mod) Remove & Replace	4	EA	\$ _____	\$ _____
608F	CDOT Curb Ramp (Type 3A) Remove & Replace	4	EA	\$ _____	\$ _____
608G	CDOT Curb Ramp (Type 4A) Remove & Replace	3	EA	\$ _____	\$ _____
608H	CDOT Curb Ramp (Type 5A) Remove & Replace	3	EA	\$ _____	\$ _____
608I	Detectable Warning 2' X 3' (STICK ON)	3	EA	\$ _____	\$ _____
SUBTOTAL THIS PAGE				\$ _____	\$ _____