



PIPE BURST NOTES:

1. PIPE SHALL BE X" ID EHMW HDPE PE3804.
2. PAVEMENT REMOVAL, EXCAVATION, BEDDING, STRUCTURAL BACKFILL, AND COMPACTION SHALL BE INCLUDED IN THE PRICE OF THE PIPE BURST.
3. COMPACTION SHALL BE IN ACCORDANCE WITH THE REQUIREMENTS OF SECTION 720 OF THE SPECIAL PROVISIONS.
4. BRACING, SHORING, SHEETING, ETC. SHALL BE IN ACCORDANCE WITH ALL STATE & OSHA REQUIREMENTS. SHORING SHALL BE CONSIDERED INCIDENTAL TO STORM SEWER CONSTRUCTION & IS TO BE INCLUDED IN THE UNIT PRICE OF THE PIPE BURST.
5. CONSTRUCTION OF THE NEW CONNECTION TO THE SEWER MAIN SHALL BE MADE IN THE PRESENCE OF A WHEAT RIDGE SANITATION DISTRICT INSPECTOR. CALL TOM REPP, CARE OF MARTIN/MARTIN ENGINEERS AT 303-431-6100 AT LEAST 48 HOURS IN ADVANCE TO SCHEDULE AN INSPECTION.
6. THE CONTRACTOR MUST OBTAIN A LICENSE BY THE WHEAT RIDGE SANITATION DISTRICT TO PERFORM CONNECTION WORK AT THE SANITARY SEWER MAIN.

SCALE: 1"=2'