



NON-RIGID PIPE TRENCH BACKFILL (FOR METAL AND PLASTIC STORM SEWER PIPE)

PIPE TRENCH NOTES:

1. PAVEMENT REMOVAL, EXCAVATION, BEDDING, STRUCTURAL BACKFILL, AND COMPACTION SHALL BE INCLUDED IN THE PRICE OF THE PIPE.
2. COMPACTION SHALL BE IN ACCORDANCE WITH THE REQUIREMENTS OF SECTION 720 OF THE SPECIAL PROVISIONS.
3. BRACING, SHORING, SHEETING, ECT. SHALL BE IN ACCORDANCE WITH ALL STATE & OSHA REQUIREMENTS. SHORING SHALL BE CONSIDERED INCIDENTAL TO STORM SEWER CONSTRUCTION & IS TO BE INCLUDED IN THE UNIT PRICE OF THE PIPE.